

CONSTRUCTION NOTICE

WHAT: Installation of Geotechnical Monitoring Instrumentation

WHERE: Hudson County Shaft Site and Haul Road

WHEN: June 2, 2025 – June 20, 2025
7:00 AM to 3:30 PM (Weekdays)

Beginning June 2, Schiavone Lane Dragados JV (SLDJV) will be installing Observation Wells and Vibrating Wire Clusters at the Hudson County Shaft site.

- 4 Observation Wells will measure the elevation of the groundwater surrounding the shaft excavation.
- 6 Vibrating Wire Clusters will monitor ground settlement.
- The excavation for each observation well & vibrating wire cluster is expected to take 2 days each and will utilize a track drill rig.
- No noise exceedances are expected during the operation.



- Vibrating Wire Clusters
- Observation Wells

Questions or Concerns?

24/7 Hotline: 1-800-444-1050

Email: PalisadesTunnel@gatewayprogram.org

General Project Overview – The Palisades Tunnel Project will use tunnel boring machines (TBMs) to excavate two parallel tunnels—measuring approximately 5,100 feet long with an inside diameter of 25 feet—through the rock formations of the Palisades. The project also involves building the new Hudson County Shaft, which will be used to remove the TBMs when digging is complete. The project contractor is Schiavone Dragados Lane Joint Venture (SLDJV).

www.gatewayprogram.org

